

Cost-Effective Hybrid Constructed Wetlands for Landfill Leachate Reclamation

Sarina Ergas, Mauricio Arias, Xia Yang, Bisheng Gao, Lillian Mulligan, Xufeng Wei

Department of Civil & Environmental Engineering

11/21/2019



TAG Member	Position/Affiliation
James S. Bays	Technology Fellow, Jacobs Engineering
Kimberly A. Byer	MSW Management Division Director, Hillsborough County
Stephanie Bolyard	Research & Scholarship Prog. Manager, EREF
William J. Cooper	Prof. Emeritus, UC Irvine, Courtesy Prof. Environmental Engineering UF
Ashley Danley-Thomson	Assistant Professor, Florida Gulf Coast University
Ashley Evans	Market Area Engineer, Waste Management, Inc., Florida
Melissa Madden-Mawhir	Senior Program Analyst, FDEP
Larry E. Ruiz	Landfill Operations Manager, Hillsborough County



- ➤ Background, Hypotheses and Objectives
- > Research Plan

Lab-scale SBR

Pilot-scale CW

Reuse regulations

- > Practical specific benefits for end users
- **≻**Timeline



Problems with Landfill Leachate

- Discharge to POTWs common in Florida.
- High ammonia, recalcitrant organic matter and metal concentrations disrupt POTW processes.
- Hybrid vertical/horizontal subsurface flow constructed wetlands - cost-effective for onsite leachate treatment.




Douglas Road Landfill Leachate Treatment Wetland IN (courtesy Jim Bays Jacobs Engineering)



CWs for Landfill Leachate Treatment

- Well documented for removal of organic compounds, nitrogen and trace metals.
- Reduces leachate volume by evapotranspiration.
- Year-round warm temperatures favor plant growth and biogeochemical processes that promote good performance.
- Hybrid Vertical Flow Horizontal Flow Subsurface CWs enhances nitrification/denitrification.



Source: case study based on (Bulc, 2006)



Questions from Hinkley Research Agenda

- What innovative technologies are available to engineer wetlands capable of treating landfill leachate?
- What cost-effective pretreatment processes should the leachate undergo to meet secondary drinking water standards?
- What processes, chemicals, or plants are best suited to mitigate the negative impact of humic acids as a pretreatment process at a landfill?



Guiding Hypotheses

- Addition of <u>zeolite</u>, a natural mineral with a high NH₄⁺ affinity, to VF-CW media reduces free ammonia toxicity to microorganisms and enhances biological nitrogen removal.
- Addition of <u>biochar</u>, a low-cost material produced from organic feedstocks such as wood chips, to HF-CW media enhances plant growth and retains recalcitrant organic matter, such as humic acids, to enhance its heterotrophic biodegradation.
- Adsorbent amended hybrid CWs can provide a cost-effective and low complexity landfill leachate treatment method compared with conventional onsite leachate treatment systems.



Research Objectives


- 1. Design lab-scale sequencing batch reactors with and without adsorbent to investigate the effects of adsorbent and aid pilot-scale CW design.
- Compare conventional and adsorbent amended hybrid CW performance for landfill leachate treatment in pilot study;
- Develop a numerical process model that can be used to predict the performance of the of the hybrid CWs under varying operational and leachate characteristics; and
- 4. Carry out a preliminary assessment of post-treatment requirements for reuse applications.



Natural Zeolite Minerals

- Porous aluminosilicate minerals.
- High cation exchange capacity and selectivity for NH₄⁺ and K
 +.
- Clinoptilolite most abundant and commonly used zeolite.
- Chabazite more expensive but higher NH₄⁺ capacity.
- Widely used as chemical sieve, food and feed additive, odor control (cat litter).








- Low-cost material produced by pyrolysis of organic feedstock (e.g., wood chips) at high temperature under O₂ limitations.
- High surface area, cation exchange capacity, moisture holding capacity.
- Improves productivity of agricultural soils.
- Enhances growth of beneficial microorganisms.






COD removal in landfill leachate by biochar.



Adsorption and bioregeneration





Hillsborough County's Southeast Landfill

- Class 1 landfill, waste tire processing, & composting operations.
- Partial onsite leachate treatment by activated sludge BNR with glycerol addition.
- Leachate hauled to county POTW.
- Pilot CWs will be housed in containment area adjacent to the leachate treatment.
- County interested in the potential implementation at adjacent wetlands.
- Operations staff enthusiastic about project.

			Hataaataal	Tuestad
Parameter		Units	Untreated Leachate	Treated Leachate
р	Н	mg/L	7.6-7.9	7.2-8.2
Co	nd.	umhos/cm	12,700-15,300	14,200-16,200
CC	DD	mg/L	450-1500	600-2000
ВС	D ₅	mg/L	50-70	2-44
Amm	nonia	mg/L	300-450	NP
	Sb	μg/L	40-430	3
As Retals Ba Cu Pb	As	μg/L	8-80	7
	Ва	μg/L	50-1300	57
	Cu	μg/L	30-190	12
	Pb	μgL	15-160	0.52
	Zn	μg/L	40-100	21

NP: data not provided.



Lab-scale experimental design



LECA LECA Zeolite Zeolite Biochar

Different wetland substrates for microbial growth





LECA




Zeolite




Biochar



Lab-scale sequencing batch reactor operation




6-day Acclimation stage to establish biofilm






Lab-scale experimental results --- COD



- Biochar column has highest COD removal efficiency.
- The addition of zeolite does not improve the COD removal.




Lab-scale experimental results --- NH₄+-N



All three columns have high ammonia removal, indicating good nitrification efficiency.




Lab-scale experimental results --- NO₂-N



In biochar column, in anoxic phase, nitrite concentration is higher due to lack of available carbon source.



Lab-scale experimental results --- NO₃-N




- ➤ In biochar column, in aerobic phase, lack of COD causes higher NO₃⁻.
- In clay column, clay and zeolite column, the N species conc. are similar, zeolite addition does not make significant

difference.




Lab-scale experimental results --- DO




In anoxic phase, DO in three columns are high due to recirculation, nitrification might occur along with denitrification.



Lab-scale experimental results --- Color





- Raw Leachate
 - LECA e Effluent
- LECA Zeolite Effluent
- LECA Zeolite Biochar Effluent


- Biochar column has highest color removal.
- In biochar column, bioregeneration of biochar may occur but not release COD into the

effluent.



Pilot-scale CW design


- Adsorption isotherm studies to determine zeolite & biochar fractions with expanded clay.
- 3 pilot-scale hybrid VF-HF CWs.
- Planted with low cost, low maintenance, leachate tolerant plants



Pilot system schematic (not to scale).

CW	V-CW medium	HF-CW medium	Feed
CW#1	LECA	LECA	Raw
CW#2	LECA + zeolite	LECA + biochar	Raw
CW#3	LECA + zeolite	LECA + biochar	Treated

LECA= lightweight expanded clay aggregate






Pilot CW Monitoring & Modeling

- Biweekly measurements of pH, alkalinity, TSS/VSS, N and P species, sCOD, BOD5, UV254, full wavelength scans, metals.
- Logging sensors for water level, temperature and conductivity at hourly time steps.
- CW numerical process model to predict daily and long term N and organic carbon performance under varying operational, media and leachate characteristics.


Pollutant Mass Balance

$$\frac{\Delta M_y}{\Delta t} = Q_i C_i - (Q_o C_y) - (\alpha ETx A_y C_y) - (k A_y (C_y - C^*))$$





CW performance comparison





Regulations and recommendations of water reuse


	er Quality rameter	Urban reuse	Agricultural reuse	Industrial reuse	Aquifer recovery
Example		Municipal irrigation	Agricultural irrigation	(noling	
BOD ₅ (mg/L ann avg)		20	20	20	20
рН		NS	7~8	7.9 ~ 8.7	6.5 ~ 9.2
Conductivity (µs/cm)		NS	< 1,360	< 1,120	< 1,000
Total	N (mg/L)	< 10	NS	< 2.3	NS
NO ₃ -	- N (mg/L)	NS	< 9.34	< 0.1	< 15
NH ₄ -	- N (mg/L)	NS	< 0.02	< 0.25	< 1.5
	As (mg/L)	< 0.1	NS	< 0.006	NS
Heavy	Cu (mg/L)	< 0.2	< 0.003	< 0.003	< 0.1
metals	Pb (mg/L)	< 5	NS	< 0.003	< 0.02
	Zn(mg/L)	< 2	NS	< 0.021	< 0.2


Notes: NS= not specified by the Florida state's reuse regulation; avg = average; ann = annual.



Post Treatment Requirements for Reuse

- Preliminary assessment of posttreatment requirements for reuse.
- Consider irrigation, industrial (e.g., cooling water), aquifer recharge, surface water augmentation, direct & indirect potable reuse.
- Post-treatment requirements coagulation-flocculationsedimentation-filtration, DAF, AOP, biofiltration, IX, GAC and membrane processes.





From Schimmoller *et al.* (2015) Triple bottom line costs for multiple potable reuse treatment schemes, *J. Royal Society Chem*.



Practical Specific Benefits for End Users

"The treatment of landfill leachate is a big issue both economically and environmentally for most landfills and wastewater treatment plants."

- Hinkley Center Research Agenda

- Hybrid CWs for onsite treatment have low complexity, low capital and O&M costs and proven long-term performance for removal of organic matter, nutrients and metals from landfill leachate.
- Addition of low-cost adsorbent materials, clinoptilolite and biochar, can reduce system land requirements and improve effluent quality.
- Effluents from the proposed CWs can be safely discharged to POTWs or treated further to meet reclaim water standards.



Project Timeline and Milestones


Task	Q1	Q2	Q3	Q4	Deliverable
Lab scale SBR design & operation					Three SBRs
Isotherm studies					Data for CW studies
CW construction & start up					Three pilot CWs
Pilot operation & modeling					Process model, Journal publication
Reuse assessment					Journal publication
Education & outreach					K-12 and USF students, professionals & community members
Quarterly & final reports					Reports for Hinkley and USF websites



Research Team










Project Description: The dominant landfill leachate management method in Florida is discharge to municipal wastewater treatment plants. However, high concentrations of recalcitrant organic compounds, ammonia and metals in leachate interfere with wastewater treatment processes. Prior studies have shown that sub-surface flow hybrid constructed wetlands (CWs) that combine vertical flow (VF) and horizontal flow (HF) are a cost-effective method for onsite landfill leachate treatment; however, information is limited on the ability of these system to meet reclaim standards for irrigation, industrial, aquifer recharge, surface water augmentation or direct and













Questions?









Overall NH₄- -N reduction

